VPDES PERMIT PROGRAM FACT SHEET

FILE NO: 698

This document gives pertinent information concerning the VPDES Permit listed below. This permit is being processed as a <u>Minor MUNICIPAL</u> permit.

EXPIRATION DATE: April 2, 2014 1. PERMIT NO.: VA0060526 2. FACILITY NAME AND LOCAL MAILING FACILITY LOCATION ADDRESS (IF DIFFERENT) ADDRESS St. Brides Correctional Center/ Environmental Services Unit (SBCC/ESU) SBCC, 701 Sanderson Road VADOC, ERO 1001 Obici Industrial Blvd., Suite F Suffolk, VA 23434 Chesapeake, VA 23328-6482 CONTACT AT FACILITY: CONTACT AT LOCATION ADDRESS NAME: Dallas L. Phillips NAME: Charles Brown TITLE: Environmental Services Manager TITLE: Treatment Plant Supervisor **PHONE:** (757) 925-2212 **PHONE:** (757) 296-3364 EMAIL: EMAIL: 3. OWNER CONTACT: (TO RECEIVE PERMIT) CONSULTANT CONTACT: NAME: Timothy G. Newton NAME: TITLE: Environmental Services Director FIRM NAME: COMPANY NAME: VDOC ADDRESS: ADDRESS: 6900 Atmore Drive Richmond, VA 23225 **PHONE:** (804)887-8069 PHONE: (EMAIL: EMAIL: PERMIT DRAFTED BY: DEQ, Water Permits, Regional Office 4. Permit Writer(s): Melinda Woodruff Date(s): 12/12/13 7440 1/31/14, 2/18/14 Date(s): 2/11/14, 2/19/14 Reviewed By: Deanna Austin PERMIT ACTION: (x) Reissuance () Revoke & Reissue () Owner Modification () Issuance () Board Modification () Change of Ownership/Name [Effective Date: 6. SUMMARY OF SPECIFIC ATTACHMENTS LABELED AS: Site Inspection Report/Memorandum Attachment 1 Attachment 2 Discharge Location/Topographic Map Attachment 3 Schematic/Plans & Specs/Site Map/Water Balance TABLE I - Discharge/Outfall Description Attachment Attachment TABLE II - Effluent Monitoring/Limitations Effluent Limitations/Monitoring Rationale/Suitable Attachment 6 Data/Antidegradation/Antibacksliding Attachment 7 Special Conditions Rationale Attachment 8 Receiving Waters Info./Tier Receiving Waters Info./Tier Determination/STORET Data/Stream Modeling/303(d) Listed Segments Attachment 9 TABLE III(a) and TABLE III(b) - Change Sheets Attachment 10 Chronology Sheet Attachment Public Participation

APPLICATION COMPLETE: December 12, 2013

PERMIT CHARACTERIZATION: (Che	eck as many as appropriate)
<pre>(x) Existing Discharge () Proposed Discharge (x) Municipal SIC Code(s) 9223 () Industrial SIC Code(s) () POTW () PVOTW () Private () Federal (x) State () Publicly-Owned Industrial</pre>	<pre>(x) Effluent Limited (x) Water Quality Limited () WET Limit () Interim Limits in Permit () Interim Limits in Other Document () Compliance Schedule Required () Site Specific WQ Criteria () Variance to WQ Standards () Water Effects Ratio (x) Discharge to 303(d) Listed Segment () Toxics Management Program Required () Toxics Reduction Evaluation () Storm Water Management Plan () Pretreatment Program Required () Possible Interstate Effect () CBP Significant Dischargers List</pre>
RECEIVING WATERS CLASSIFICATION	N: River basin information.
River Mile: 53XAHO Basin: Chowan Subbasin: Albema Section: 1C	
FACILITY DESCRIPTION: Describ originate.	e the type facility from which the discharges
EXISTING municipal discharge r sewage from a State correction	esulting from the discharge of treated domestic al center.
LICENSED OPERATOR REQUIREMENTS	: () No (X) Yes Class: II
RELIABILITY CLASS: In	dustrial Facility - NA
SITE INSPECTION DATE: January	7, 2010 <u>REPORT DATE</u> : January 8, 2010
Performed By: Clyde Gantt, Com	pliance
SEE ATTACHMENT 1	
	ION: Provide USGS Topo which indicates the discharge discharger(s) to the receiving stream, water intakes,
Name of Topo: Moyock	Quadrant No.: 2C SEE ATTACHMENT 2

14. ATTACH A SCHEMATIC OF THE WASTEWATER TREATMENT SYSTEM(S) [IND. & MUN.]. FOR INDUSTRIAL FACILITIES, PROVIDE A GENERAL DESCRIPTION OF THE PRODUCTION CYCLE(S) AND ACTIVITIES. FOR MUNICIPAL FACILITIES, PROVIDE A GENERAL DESCRIPTION OF THE TREATMENT PROVIDED.

<u>Narrative</u>: Influent equalization basin, four sequencing batch reactor (SBR) basins for treatment process (with fine bubble diffusers, jet mixing headers, floating controls, two ultraviolet disinfection basins, three aerobic digesters, dewatering by plate and frame sludge press, sludge transported to Southampton CC by contractor for land application. Post aeration. Programmable Logic controller (PLC) in operations building.

SEE ATTACHMENT 3

15. DISCHARGE DESCRIPTION: Describe each discharge originating from this facility.

SEE TABLE I (OR CAN SUBSTITUTE PAGE 2C) - SEE ATTACHMENT 4

16. COMBINED TOTAL FLOW:

TOTAL:	0.544	MGD	(for	public	notice)
DES	IGN FLOW:		544	MGD	(MUN.)

- 17. STATUTORY OR REGULATORY BASIS FOR EFFLUENT LIMITATIONS AND SPECIAL CONDITIONS: (Check all which are appropriate)

 - X State Water Control Law
 - X Clean Water Act
 - X VPDES Permit Regulation (9 VAC 25-31-10 et seq.)
 - X EPA NPDES Regulation (Federal Register)
 - EPA Effluent Guidelines (40 CFR 133 or 400 471)
 - X Water Quality Standards (9 VAC 25-260-5 et seq.)
 - X Wasteload Allocation from a TMDL or River Basin Plan
- 18. <u>EFFLUENT LIMITATIONS/MONITORING</u>: Provide all limitations and monitoring requirements being placed on each outfall.

SEE TABLE II - ATTACHMENT 5

19. EFFLUENT LIMITATIONS/MONITORING RATIONALE: Attach any analyses of an outfall by individual toxic parameter. As a minimum, it will include: statistics summary (number of data values, quantification level, expected value, variance, covariance, 97th percentile, and statistical method); wasteload allocation (acute, chronic and human health); effluent limitations determination; input data listing. Include all calculations used for each outfall and set of effluent limits and those used in any model(s). Include all calculations/documentation of any antidegradation or antibacksliding issues in the development of any limitations; complete the review statements below. Provide a rationale for limiting internal waste streams and indicator pollutants. Attach chlorine mass balance calculations, if performed. Attach any additional information used to develop the limitations, including any applicable water quality standards calculations (acute, chronic and human health).

OTHER CONSIDERATIONS IN LIMITATIONS DEVELOPMENT:

<u>VARIANCES/ALTERNATE LIMITATIONS</u>: Provide justification or refutation rationale for requested variances or alternatives to required permit conditions/limitations. This includes, but is not limited to: waivers from testing requirements; variances from technology guidelines or water quality standards; WER/translator study consideration; variances from standard permit limits/conditions.

<u>SUITABLE DATA</u>: In what, if any, effluent data were considered in the establishment of effluent limitations and provide all appropriate information/calculations.

All suitable effluent data were reviewed.

<u>ANTIDEGRADATION REVIEW:</u> Provide all appropriate information/calculations for the antidegradation review.

The receiving stream has been classified as tier 1; therefore, no further review is needed. Permit limits have been established by determining wasteload allocations which will result in attaining and/or maintaining all water quality criteria which apply to the receiving stream, including narrative criteria. These wasteload allocations will provide for the protection and maintenance of all existing uses

<u>ANTIBACKSLIDING REVIEW</u>: Indicate if antibacksliding applies to this permit and, if so, provide all appropriate information.

There are no backsliding issues to address in this permit (i.e., limits as stringent or more stringent when compared to the previous permit).

SEE ATTACHMENT 6

20. SPECIAL CONDITIONS RATIONALE: Provide a rationale for each of the permit's special conditions.

SEE ATTACHMENT 7

21. TOXICS MONITORING/TOXICS REDUCTION AND WET LIMIT SPECIAL CONDITIONS RATIONALE:

Provide the justification for any toxics monitoring program and/or toxics reduction program and WET limit.

NA

22. <u>SLUDGE DISPOSAL PLAN</u>: Provide a description of the sludge disposal plan (e.g., type sludge, treatment provided and disposal method). Indicate if any of the plan elements are included within the permit.

Sludge is transported to the VDOC Southampton Correctional Center (SHCC) for land application to sites permitted through the VDOC SHCC VPDES permit NO. VA0062499. As a back-up VDOC SBCC has a contract with the Southeastern Public Service Authority of Virginia (SPSA).

23. MATERIAL STORED: List the type and quantity of wastes, fluids, or pollutants being stored at this facility. Briefly describe the storage facilities and list, if any, measures taken to prevent the stored material from reaching State waters.

Calcium hypochlorite (HTH®) is stored on pallets in drums in the building, can only be accessed by the treatment plant operator/supervisor.

24. RECEIVING WATERS INFORMATION: Refer to the State Water Control Board's Water Quality Standards [e.g., River Basin Section Tables (9 VAC 25-260-5 et seq.). Use 9 VAC 25-260-140 C (introduction and numbered paragraph) to address tidal waters where fresh water standards would be applied or transitional waters where the most stringent of fresh or salt water standards would be applied. Attach any memoranda or other information which helped to develop permit conditions (i.e. tier determinations, PReP complaints, special water quality studies, STORET data and other biological and/or chemical data, etc.

SEE ATTACHMENT 8

25. <u>305(b)/303(d) Listed Segments</u>: Indicate if the facility discharges to a segment that is listed on the current 303(d) list and, if so, provide all appropriate information/calculations.

This facility discharges directly to an unnamed tributary which is not an impaired segment. This receiving stream segment eventually discharges to Indian Creek which has been listed in Category 5 of the 305(b)/303(d) list for non-attainment of dissolved oxygen.

EPA approved the Northwest River watershed TMDL on 4/26/2011, SWCB approved 6/25/2012 for this segment. It contains a wasteload allocation for this discharge of total phosphorus TMDL due to low dissolved oxygen impairment (Average annual load = 1877.68 kg/yr total phosphorus and Maximum daily load of 5.144 kg/day). This permit contains those same limits of total phosphorus which are in compliance with the TMDL.

The permit contains limits for DO, TSS, and TP.

26. CHANGES TO PERMIT: Use TABLE III(a) to record any changes from the previous permit and the rationale for those changes. Use TABLE III(b) to record any changes made to the permit during the permit processing period and the rationale for those changes [i.e., use for comments from the applicant, VDH, EPA, other agencies and/or the public where comments resulted in changes to the permit limitations or any other changes associated with the special conditions or reporting requirements].

SEE ATTACHMENT 9

27. NPDES INDUSTRIAL PERMIT RATING WORKSHEET:

N/A - This is a municipal facility.

28. <u>DEQ PLANNING COMMENTS RECEIVED ON DRAFT PERMIT</u>: Document any comments received from DEQ planning.

The discharge is not addressed in any planning document but will be included when the plan is updated.

29. <u>PUBLIC PARTICIPATION</u>: Document comments/responses received during the public participation process. If comments/responses provided, especially if they result in changes to the permit, place in the attachment.

<u>VDH/DSS COMMENTS RECEIVED ON DRAFT PERMIT</u>: Document any comments received from the Virginia Dept. of Health and the Div. of Shellfish Sanitation and noted how resolved.

By letter dated 12/3/13, the VDH provided the following comments: The raw water intake for the Northwest River System waterworks is located approximately 6 miles downstream of the discharge. This should be a sufficient distance to minimize the impacts of the discharge.

The DSS has no comments on the application/draft permit.

OTHER COMMENTS RECEIVED FROM RIPARIAN OWNERS/CITIZENS ON DRAFT PERMIT: Document any comments received from other sources and note how resolved.

The application and draft permit have received public notice in accordance with the VPDES Permit Regulation, and no comments were received.

OR

The application and draft permit have received public notice in accordance with the VPDES Permit Regulation. Section 9 VAC 35-31-310 of the VPDES Permit Regulation states, in part, "The Board shall hold a public hearing whenever it

finds, on the basis of requests, a significant degree of public interest in a draft permit(s)."

DESCRIBE PN COMMENTS AND RESOLUTIONS. PROVIDE PUBLIC HEARING DATE AND REFERENCE BACKGROUND MEMORANDUM, IF APPROPRIATE.

PUBLIC NOTICE INFORMATION: Comment Period: Start Date End Date

Persons may comment in writing or by e-mail to the DEQ on the proposed reissuance of the permit within 30 days from the date of the first notice. Address all comments to the contact person listed below. Written or e-mail comments shall include the name, address, and telephone number of the writer, and shall contain a complete, concise statement of the factual basis for comments. Only those comments received within this period will be considered. The Director of the DEQ may decide to hold a public hearing if public response is significant. Requests for public hearings shall state the reason why a hearing is requested, the nature of the issues proposed to be raised in the public hearing and a brief explanation of how the requestor's interests would be directly and adversely affected by the proposed permit action.

All pertinent information is on file and may be inspected, and arrangements made for copying by contacting Melinda Woodruff at: Department of Environmental Quality (DEQ), Tidewater Regional Office, 5636 Southern Boulevard, Virginia Beach, VA 23462. Telephone: 757-518-2174 E-mail: Melinda.Woodruff@deq.virginia.gov

Following the comment period, the Board will make a determination regarding the proposed reissuance. This determination will become effective, unless the Director grants a public hearing. Due notice of any public hearing will be given.

30. ADDITIONAL FACT SHEET COMMENTS/PERTINENT INFORMATION:

ATTACHMENT 1 SITE INSPECTION REPORT/MEMORANDUM



COMMONWEALTH of VIRGINIA

DEPARTMENT OF ENVIRONMENTAL QUALITY

L. Preston Bryant, Jr. Secretary of Natural Resources TIDEWATER REGIONAL OFFICE
5636 Southern Boulevard, Virginia Beach, Virginia 23462
(757) 518-2000 Fax (757) 518-2009
www.deq.virginia.gov

David K. Paylor Director

Francis L. Daniel Regional Director

February 12, 2010

Mr. Dallas L. Phillips Environmental Services Unit VDOC, 1001 Obici Industrial Blvd., Suite F Suffolk, VA 23434

Re: Inspection Report

Saint Brides Correctional Center STP (VA0060526)

Dear Mr. Phillips:

Enclosed is a copy of the report prepared for the inspection conducted at your facility on January 7, 2010. Please note the deficiencies cited in this report and implement appropriate corrective measures in order to ensure continued permit compliance. Within twenty (20) days of receipt of this report, you are required to submit a letter documenting that the necessary corrections have been made.

If you have any questions regarding this report, please feel free to contact me at the above address, telephone (757) 518-2114 or email clyde.gantt@deq.virginia.gov.

Sincerely,

Clyde K. Gantt

VPA/VPDES Permit Inspector

Enclosure

cc:

DEQ/OWCP: Steve Stell

DEQ/TRO: File

DEQ WASTEWATER FACILITY INSPECTION REPORT PREFACE

VPDES/State Certif	ication No.	(RE) Issu		PREFAC ate	Amendment Da	nte		Expiration I	Date
VA006052			3, 2009		N/A		April 2, 2014		
	ility Name		Address			Telephone Number			
VDOC Saint Brides Cor		er	701 Sa	nderso	n Rd., Chesapeake, VA	2328		21-6600 X 28	
Ow	vner Name				Address			Telephone Nu	
VA Dept. of Corrections			1001 (Obici Inc	dustrial Blvd., Suffolk	, VA		25-2212	
	nsible Official				Title			Telephone Nu	mber
Dallas L. Phillips			Envir	onment	al Services Manager		(757) 9	25-2212	
Respon	sible Operator			Opera	tor Cert. Class/number			Telephone Nu	mber
Charles Brown			Class	I / 00014	140		(757) 4	21-6600 X 28	60
TYPE OF FACILITY:			1						
	DOMESTI	С			***************************************	INDU	STRIAI		
Federal		Major			Major		***************************************	Primar	у
Non-federal		Minor	······································	X	Minor		Secondary		ıry
INFLUENT CHARACTE	RISTICS:			1	DESIGN:				
	70	Flow		***************************************	0.544				
		Population Ser							
		Connections Ser			2	2			
		BOD ₅		97%					
		TSS			97.5%				
EFFLUENT LIMITS: SPE	CIFY UNITS								
Parameter	Min.	Avg.	M	ax.	Parameter	Mir	ı.	Avg.	Max.
Flow		0.544			E. Coli			126	
рН	6.0		9.	.0	CBOD			10	15
TSS		10	1	5					
D.O.	3.0								
TKN		3.0	4.	.5					
		Receiving Stream	am		Unnamed Trb –	NW Rive	r		
		Basin			Chowa	1			
	I	Discharge Point (L	ONG)		3944611	E			
		Discharge Point (LAT)		0515291	٧			

VPDES NO. VA0060526

REV 5/00

DEQ WASTEWATER FACILITY INSPECTION REPORT PART 1

Inspection date: January 7, 2010			Date form co	mpleted: January 8, 2010		
Inspection by: Clyde Gantt			Inspection agency: DEQ			
Time spent: 7 Hours				No		
Reviewed by: Kenneth	T. Raum		Scheduled: `	⁄es		
Present at inspection:	Mr. Charles E. Brown – F	Plant Manager (757) 421-6	600 X2860			
TYPE OF FACILITY:	Domestic		Industrial			
[] Federal [] Nonfederal	[] Major [X] Minor		[] Major [] Minor	[] Primary [] Secondary		
Type of inspection:						
[X] Routine [] Compliance/Assistal [] Reinspection	nce/Complaint		Date of last in Agency: DEG	nspection: Dec. 8, 2005 Q		
Population served: 200	0 Conne	ctions served: 2				
Last month grab: (Influent)Month: Dece	TSS - 142 mg/L mber, 2009 Other - pH: 7.1 S.U.	Flow - 0.1831 MGD				
Last month Comp.:	TSS - 1 mg/L	Flow – 0.203 M	GD			
(Effluent)	Other: pH - 6.9 - 7.4 S	S.U., TKN - 1.05 mg/l				
First Quarter average: (Effluent)	TSS - 1.2 mg/L	Flow – 0.188 M	GD			
(Emuent)	Other: pH - 6.6 - 7.6 S	S.U., TKN - 1.0 mg/l				
DATA VERIFIED IN PR	EFACE	[X] Updated [] No o	changes			
Has there been any nev	v construction?	[]Yes	[X] No			
If yes, were plans and s	pecifications approved?	[]Yes	[]No	[X]NA		
DEQ approval date:						

(A) PLANT OPERATION AND MAINTENANCE

1. Class and number of licensed operators:	I – 1 (#1449), II - 1, III –	· 1, IV - 1, Traine	e - 2
2. Hours per day plant is manned: 9 Hours/Day			
3. Describe adequacy of staffing.	[]Good	[X] Average	[] Poor
4. Does the plant have an established program for tr	aining personnel? []Yes	[X*] No	
5. Describe the adequacy of the training program.	[]Good	[X] Average	[] Poor
6. Are preventive maintenance tasks scheduled?	[X]Yes	[]No	
7. Describe the adequacy of maintenance.	[]Good	[X] Average	[]Poor*
Does the plant experience any organic/hydraulic of the second of th	overloading? [] Yes	[X] No	
9. Any bypassing since last inspection?	[]Yes	[X] No	
10. Is the standby electric generator operational?	[X] Yes	[] No*	[] NA
11. Is the STP alarm system operational?	[X] Yes	[] No*	[] NA
12. How often is the standby generator exercised? Nower Transfer Switch? Weekly	Weekly Alarm System? Week	ly	
13. When was the cross connection control device la	ast tested on the potable w	ater service? Do	ec. 2, 2009
14. Is sludge being disposed in accordance with the	approved sludge disposal [olan? [X] Ye	es[]No []NA
15. Is septage received by the facility? Is septage loading controlled? Are records maintained?	[] Yes [] Yes [] Yes	[X] No [] No [] No	
16. Overall appearance of facility:	[X] Good	[] Average	[] Poor

Comments: *Operators attend DEQ training as available and as needed.

(B) PLANT RECORDS

1	. Which of the following records does the plant main	ntain?		
	Operational Logs for each unit process Instrument maintenance and calibration Mechanical equipment maintenance Industrial waste contribution (Municipal Facilities)	[X] Yes [X] Yes [X] Yes [] Yes	[] No [] No [] No [] No	[] NA [] NA [] NA [X] NA
2	. What does the operational log contain?			
	[] Visual observations[X] Laboratory results[] Control calculations	[X] Flow meas [X] Process ac [] Other (spe	djustments	
	Comments:			
3.	What do the mechanical equipment records contain	in?		
	[X] As built plans and specs[X] Manufacturers instructions[X] Lubrication schedules	[] Spare parts [] Equipment [] Other (spe	/parts suppliers	
	Comments:			
4.	What do the industrial waste contribution records of (Municipal Only)?	contain		
	[] Waste characteristics [] Impact on plant	[] Locations a [] Other (spe	and discharge typcify)	oes
	Comments:			
5.	Which of the following records are kept at the plant	and available to	personnel?	
	[X] Equipment maintenance records[] Industrial contributor records[X] Sampling and testing records	[X] Operational		
6.	Records not normally available to plant personnel a	and their location	:	
7.	Were the records reviewed during the inspection?		[X] Yes	[] No
8.	Are the records adequate and the O & M Manual c	urrent?	[X] Yes	[] No
9.	Are the records maintained for the required 3-year t	ime period?	[X] Yes	[] No
Com	ments:			

[] NA

[]NA

(C) SAMPLING 1. Do sampling locations appear to be capable of providing representative samples? [X] Yes [] No* 2. Do sample types correspond to those required by the VPDES permit? [X] Yes [] No* 3. Do sampling frequencies correspond to those required by the VPDES permit? [X] Yes [] No* 4. Are composite samples collected in proportion to flow? [X] Yes [] No* 5. Are composite samples refrigerated during collection? [X] Yes [] No* 6. Does plant maintain required records of sampling? [X] Yes [] No* 7. Does plant run operational control tests? [X] Yes [] No Comments:

6.	Does plant maintain required reco	rds of sampling?			[X] Yes	[] No*
7.	Does plant run operational control	I tests?			[X] Yes	[] No
Com	ments:					
(D) T	ESTING					
1.	Who performs the testing?	[X] Plant	[] Central Lab	[X] C	ommercial L	.ab
	Name: TKN analysis performed by	/ Jennings Labs.	_			
If pla	ant performs any testing, comple	te 2-4.				
2.	What method is used for chlorine	analysis? N/A				
3.	Does plant appear to have sufficient	nt equipment to p	erform required t	ests?	[]Yes	[] No*
4.	Does testing equipment appear to	be clean and/or o	pperable?		[]Yes	[] No*
Com	ments:					
(E) F	OR INDUSTRIAL FACILITIES WITI	H TECHNOLOGY	BASED LIMITS	ONLY		
1.	Is the production process as descr	ibed in the permi	t application? (If [] No	no, describe c	hanges in co	omments)
2.	Do products and production rates of	correspond as pro	ovided in the perr	mit application? [] NA	? (If no, list d	lifferences)
3.	Has the State been notified of the o	changes and thei	r impact on plant [] No*	effluent? Date) :	

Comments:

Problems identified at last inspection:	Corrected	Not Corrected
1. None	[]	[]
2.	[]	[]
3.	[]	[]
4.	[]	[]

SUMMARY

Comments:

- 1. The St. Brides pump station does not have the required alarm system battery back-up.
- 2. There is no testing done to prove that the sludge meets Class B requirements for biosolids.
- 3. The treatment plant was in overall good condition and appears well maintained.

Recommendations for action:

- 1. 9VAC25-790-420.D. requires a backup power supply for the alarm system in a Reliability Class I facility with dual electrical feed sources. The St. Brides pumps station must be modified to include a backup power supply.
- 2. 9VAC25-31-560 requires pathogen reduction and vector attraction reduction requirements for biosolids. 9VAC25-31-710.B & D. provides the pathogen reduction options for Class B sludge. One of these options must be implemented and documented.
 - Please note that the vector attraction reduction requirement is met by VDOC Southampton using 9VAC25-31-720.B.10.
- 3. The Sludge Management Plan (SMP) for this facility must be revised to document the pathogen reduction and vector attraction methods used to meet the requirements for Class B biosolids.



COMMONWEALTH of VIRGINIA

DEPARTMENT OF ENVIRONMENTAL QUALITY

Doug Domenech Secretary of Natural Resources TIDEWATER REGIONAL OFFICE 5636 Southern Boulevard, Virginia Beach, Virginia 23462 (757) 518-2000 Fax (757) 518-2009 www.deq.virginia.gov

David K. Paylor Director

Francis L. Daniel Regional Director

February 10, 2010

Mr. Dallas L. Phillips VA Dept. of Corrections – ESU 1001 Obici Industrial Blvd., Suite F Suffolk, VA 23434

Re: Laboratory Inspection

Saint Brides Correctional Center STP (VA0060526)

Dear Mr. Phillips:

Enclosed is a copy of the inspection report for the laboratory evaluation conducted on January 7, 2010. Before leaving the facility that day I reviewed the deficiencies found during the inspection and discussed the required corrective measures. Please note that the Laboratory Evaluation Section of the report identifies that the method of analysis for E. Coli, the Laboratory Records Section and the Laboratory Equipment Section still require correction. The report identifies the specific deficiencies and makes recommendations for corrective measures.

In view of the significance attached to proper sampling and analysis of samples for use in complying with the terms of your VPDES/VPA permit, please review the attached report and make the appropriate corrections to ensure permit compliance. To avoid possible enforcement action, within fifteen (15) days of receipt of this letter send a written notification to this office of the corrective measures that you have implemented. If you have not taken corrective action and/or responded to this office in writing by the above deadline, this matter will be referred to the Regional Compliance Auditor and a Warning Letter (WL) may be issued.

If you have any questions regarding this report, please contact me or Mr. Kenneth T. Raum at the above address or telephone (757) 518-2114, or email clyde.gantt@deq.virginia.gov.

Sincerely,

Clyde K. Gantt

Environmental Specialist II

Enclosure

DEPARTMENT OF ENVIRONMENTAL QUALITY - WATER DIVISION LABORATORY INSPECTION REPORT

	~~~~	······································	10/01		•			
FACIL	ITY NO:	INSPECTION DATE:	PREVIOUS INSP. DA	TE:	PREVIOUS EVA	LUATION	<b>1</b> :	TIME SPENT:
VA00	60526	January 7, 2010	December 8, 2005		Deficienci	ies 8 Hours		8 Hours
NAME/	ADDRESS	OF FACILITY:	FACILITY CLASS:	FA	CILITY TYPE:			ANNOUNCED
	Saint Bride	es Correctional Center	() MAJOR	(X)	MUNICIPAL		(X)	ISPECTION? YES NO
	eake, VA		(X) MINOR	()	INDUSTRIAL	-		
			() SMALL		FEDERAL		IN	SCHEDULED SPECTION?
			() VPA/NDC		COMMERCIAL	IAR		YES NO
INCDE	TOD/e\.			1			**	
Clyde C	CTOR(S): Gantt		REVIEWERS: Kenneth T. Raum		PRESENT AT INS Mr. Charles Brown			ger
		LABORATO	RY EVALUATION				DEFICI	ENCIES?
		The second secon				Υe	s	No
LABOR	ATORY R	ECORDS		,		Х		
GENER	RAL SAMF	LING & ANALYSIS					***************************************	X
LABOR	RATORY E	QUIPMENT				Х		
DISSOL	_VED OXY	GEN ANALYSIS PROCE	DURES					х
pH ANA	ALYSIS PE	ROCEDURES						X
TOTAL	SUSPEN	DED SOILDS ANALYSIS F	PROCEDURES					Х
CARBO	NACEOU	S BIOCHEMICAL OXYGEN	N DEMAND ANALYSIS P	ROCE	EDURES			Х
E. COLI	I ANALYS	IS PROCEDURES				Х	······································	
***************************************								
	<del></del>							
		QUA	LITY ASSURANCE/QUA	LITY	CONTROL			
Y/N	QUALITY	ASSURANCE METHOD	PARAMETERS			FREQ	UENC	Υ
Х	REPLIC	ATE SAMPLES	TSS			EVER	Y 2 A	VALYSIS
	SPIKED	SAMPLES						
Х	STANDA	ARD SAMPLES	GGA, TSS, pH			YEAR	LY	
	SPLIT S	AMPLES						
	SAMPLE	BLANKS						
	SAMPLE OTHER	BLANKS						
	OTHER	E BLANKS R QA DATA?	RATING: () N	lo Def	ficiency () Deficie	ency (	X) NA	

		*****		FACILITY #	#: VA006	0526
LABORATORY RECORDS SECTION						
LABORATORY RECORDS INCLUDE TH	E FOLLOWING:					
X SAMPLING DATE X SAMPLING TIME X SAMPLE LOCATION WRITTEN INSTRUCTIONS INCLUDE THE	X ANALYSIS DATE X ANALYSIS TIME X TEST METHOD  E FOLLOWING:	X X	INSTRL INSTRL	MONITORING IMENT CALI IMENT MAIN ICATE OF A	BRATIO ITENAN	N CE
X SAMPLING SCHEDULES	X CALCULATIONS	X	ANALY	SIS PROCEI	DURES	
				YES	NO	N/A
DO ALL ANALYSTS INITIAL THEIR WOF	RK?			X		
DO BENCH SHEETS INCLUDE ALL INFO	ORMATION NECESSARY TO DETERM	MINE RES	SULTS?	X		
IS THE DMR COMPLETE AND CORREC	T? MONTH(S) REVIEWED: Dec., 200	9			Х	
ARE ALL MONITORING VALUES REQUI	RED BY THE PERMIT REPORTED?			X		
GENERAL SAMPLING AND ANALYSIS	SECTION					
		27		YES	NO	N/A
ARE SAMPLE LOCATION(S) ACCORDIN	IG TO PERMIT REQUIREMENTS?			X		
ARE SAMPLE COLLECTION PROCEDU	RES APPROPRIATE?			Х		
IS SAMPLE EQUIPMENT CONDITION A	DEQUATE?			Х		
IS FLOW MEASUREMENT ACCORDING	TO PERMIT REQUIREMENTS?			Х		
ARE COMPOSITE SAMPLES REPRESE	NTATIVE OF FLOW?			X		
ARE SAMPLE HOLDING TIMES AND PR	RESERVATION ADEQUATE?			Х		
IF ANALYSIS IS PERFORMED AT ANOT ADEQUATE? LIST PARAMETERS AND by Jennings Labs.				X		
LABORATORY EQUIPMENT SECTION						
				YES	NO	N/A
IS LABORATORY EQUIPMENT IN PROP	ER OPERATING RANGE?			Х		
ARE ANNUAL THERMOMETER CALIBRA	ATION(S) ADEQUATE?			Х		

Χ

IS THE LABORATORY GRADE WATER SUPPLY ADEQUATE?

ARE ANALYTICAL BALANCE(S) ADEQUATE?

## LABORATORY INSPECTION REPORT SUMMARY

FACILITY NAME:	FACILITY NO:	INSPECTION DATE:
VDOC Saint Brides Correctional Center	VA0060526	January 7, 2010
LABORATORY EVALUATION:	(X) Deficiencies	<u> </u>
	( ) No Deficiencies	
LABORAT	ORY RECORDS	
The laboratory records section has a deficiency in DMR report the correct average is 17 n/cml. The TSS average was income.	orting. The E. Coli average was incorrectly reported as 0.7 mg/l; the co	orrectly reported as 16 n/cml; rrect average is 1.0 mg/l.
GENERAL SAMP	PLING AND ANALYSIS	
The general sampling and analysis section has no deficience	ies.	
LABORATO	DRY EQUIPMENT	
The laboratory equipment section has a deficiency with the l water used meets the requirements for laboratory grade was		is no documentation that the
PARAMET	ER SUMMARY	
The analysis for the parameter of pH has no deficiencies. How longer acceptable. The bench sheet must be revised to show the		EPA Method 150.1, which is no
Dissolved The analysis for the parameter of DO has no deficiencies.	d Oxygen (DO)	
Carbonaceous Biochem The analysis for the parameter of CBOD has no deficiencies. H amount of seed used be increased from 2 ml to 3-4 ml. Also, th of GGA solution. This check is normally performed using 2%/6n increase volume of solution.	e Glucose Glutamic Acid (GGA) Che	ck was performed using 1%/3ml
Total Susper The analysis for the parameter of TSS has no deficiencies.	nded Solids (TSS)	
	E. Coli etermining analytical results. The 12	/18/09 sample result was

## ATTACHMENT 2 DISCHARGE LOCATION/TOPOGRAPHIC MAP


PWSID: 3550750 FACILITY:WELL #3

## **SWAP Zone 2 Map**

DISTRICT 20B

COUNTY/CITY: CHESAPEAKE


WATERWORKS:ST BRIDES CORRECTION CENTER






## ATTACHMENT 3


SCHEMATIC/PLANS & SPECS/SITE MAP/ WATER BALANCE



## ENVIRONMENTAL SERVICES UNIT ST. BRIDES CORRECTIONAL CENTER WASTEWATER TREATMENT PLANT

The wastewater treatment plant (WWTP) at St. Brides Correctional Center (SBCC) is the responsibility of the Virginia Department of Corrections (VDOC) Environmental Services Unit (ESU). The plant treats wastewater from both SBCC and Indian Creek Correctional Center (ICCC). Both sites have an independent sewage pumping station that transfers sewage to the WWTP. The sewage goes through a grinding and screening process at both stations before entering the plant. The WWTP is a Sequencing Batch Reactor (SBR) activated sludge process designed for .544 mgd. Flow enters the plant after passing through a muffin / auger monster unit (1). It flows into a sewage pumping station (2) that feeds the equalization basin (3). The influent is transferred into one of each of the four SBR basins (4) at different cycles made up of six phases. All four basins are equipped with a fine bubble air diffuser system, a 7.5 hp mixer, a floating decanter. and a submersible wasting pump. The computer program that controls the functioning of the SBR plant consist of six process control phases which are Mix Fill - React Fill -React - Settle - Decant - Waste Idle. The decanted supernatant flows to the filter feed well (5). This treated wastewater is pumped to the filter building (6) which consists of an Aqua Disk filtering unit. The filter has an average hydraulic loading rate of 3.54 gpm/ft^2. Flow from the filter is gravity fed to the Ultraviolet Disinfection (UV) unit (7) which consists of two banks. After passing through UV treatment, the flow enters the post aeration basin (8). From this point, the effluent flow goes through a meter and is discharged into the receiving stream (9). Sludge handling consists of three digesters (10) and a plate and frame sludge press located in the solids handling building (11). The three digesters have a holding capacity of approximately 300,000 gallons of wasted sludge. There are also six small sludge drying beds (12) for emergency use. Dewatered and stabilized biosolids are transported to Southampton Correctional Center by a contractor to be stored until land applying is ready. The dewatered flow goes to the low point punip station (13) which pumps to the head of the EQ basin. All operational controls are stationed in the control building (6) which is a separate part of the filter building. The WWTP can also be controlled by the SCADA system in the office and laboratory building (14). There is an emergency power generator (15) with an automatic transfer switch to handle the WWTP entire electrical load should a power failure occur.





BOTH FIRE ARREST SHOPS CO. MANY THE PARTY SHOPE AND ADDRESS.

## ATTACHMENT 4

TABLE I - DISCHARGE/OUTFALL DESCRIPTION

## TABLE I NUMBER AND DESCRIPTION OF OUTFALLS

OUTFALL NO.	DISCHARGE LOCATION	DISCHARGE SOURCE	TREATMENT (2)	FLOW (3)
001	36° 36′ 41″ 076° 11′ 3″	Domestic discharge from housing for incarcerated males and female inmates	Four sequencing batch reactor (SBR) basins for treatment process (with fine bubble diffusers, jet mixing headers, floating decanters, and automatic valving), filter building with disk filter and automatic controls, two ultraviolet disinfection basins, Post aeration.	0.544 MGD

- (1) List operations contributing to flow
- (2) Give brief description, unit by unit
- (3) Give maximum 30-day average flow for industry and design flow for municipal

## ATTACHMENT 5

TABLE II - EFFLUENT MONITORING/LIMITATIONS

# TABLE II - MUNICIPAL EFFLUENT LIMITATIONS/MONITORING

Part I A.1. OUTFALL # 001

DESIGN FLOW: 0.544 MGD Treated domestic sewage

Outfall Description: SIC CODE: 9223

(x) Final Timits

( ) Interim
BASIS
FOR LIMITS
т
М
8
8
3
3
m
m
m
Е

PARAMETER & UNITS	BASIS	DESIGN	¥	FFLUENT I	EFFLUENT LIMITATIONS	70	MONITORING REQUIREMENTS	NG NTS
	LIMITS	FLOW MULTIPLIER	MONTHLY	WEEKLY			***	SAMPLE
			AVERAGE	AVERAGE	MINIMOM	MAXIMUM	FREQUENCY	TYPE
Total Phosphorus (kg/d)								
[p] [e]	М		NA	NA	NA	5.14	1/Month	8-HC
Total Phosphorus Monthly								
Load (kg/m) [e]	m		NA	NL	NA	NA	1/Month	CALC
Total Phosphorus Year-to-								
Date (kg/yr) [e]	М		NA	NL	NA	NA	1/Month	CALC
Total Phosphorus Calendar						motor da Quinte prima pr	en e	
Year (kg/yr) [d][e]	m		1877.68	NA	NA	NA	1/YR	CAIC
Dissolved Copper (ug/l)						THE REAL PROPERTY OF THE PROPE		
[q]	Ж		NA	NA	NA	NL	1/6 Months	Grab
					***************************************	***************************************	***************************************	Contraction of the Contraction o

*Totalizing, Indicating & Recording Equipment

NA = NOT APPLICABLE; NL = NO LIMIT, MONITORING REQUIREMENT ONLY

1/6 Months = In accordance with the following schedule: 1st half (January 1 - June 30); 2nd half (July 1 - December

1/Year = Between January 1 and December 31.

8-HC = 8 Hour Composite samples are the combination of grab samples taken in proportion to flow over an 8 hour period of time which ensures that a representative sample is obtained for the reporting period.

In the event that there is no Upon issuance of the permit, Discharge Monitoring Reports (DMRs) shall be submitted to the regional office at the discharge for the monitoring period, then "no discharge" shall be reported on the DMR. frequency required by the permit regardless of whether an actual discharge occurs.

- See Part I.B.5. for exceeding 95% of design capacity three months consecutively. [a]
- See Parts I.B.6. and I.B.7. for quantification levels and reporting requirements, respectively.
  - See Part I.B.8. for additional instructions regarding effluent monitoring frequencies.
- Annual average limitation, based on a calculation of all samples collected during the calendar year.
  - See Part I.B.9. for additional instructions regarding total phosphorus.

The basis for the limitations codes are:

- 1. Technology (e.g., Federal Effluent Guidelines)
- 2. Water Quality Standards (9 VAC 25-260 et. seq.) 3. Best Professional Judgment

Part I.A.

- The design flow of this treatment facility is 0.544 MGD.
- There shall be no discharge of floating solids or visible foam in other than trace amounts.
  - At least 85% removal for BOD and TSS must be attained for this effluent,

## ATTACHMENT 6

EFFLUENT LIMITATIONS/MONITORING RATIONALE/SUITABLE DATA/
ANTIDEGRADATION/ANTIBACKSLIDING

## Rationale for Effluent Limitations and Monitoring Attachment 6

Outfall 001 in VPDES Permit No. VA0060526 is a municipal discharge from a wastewater treatment plant at a correctional institution. The facility serves St. Brides Correctional Center with 387 inmates and 176 employees and Indian Creek correctional Center with 999 inmates and 247 employees, average daily population can vary. The design flow of the treatment plant is 0.544 MGD which was upgraded during the last reissuance of this permit.

The discharge from Outfall 001 is continuous to an unnamed tributary of Indian Creek to the Northwest River. The receiving waters were assigned a Tier I classification. This assignment requires the effluent limits to comply with water quality standards at a minimum, see Attachment 8. These waters were further assigned Class II waters with special standards for Public Water Supply. (The raw water intake for the Northwest River waterworks is located approximately 6 miles downstream of the discharge.)

The limits for  $CBOD_5$ , TSS, TKN, and DO were applied by the assignment of swamp and marsh waters to the unnamed tributary. I have attached the Memo dated March 9, 1987 for the Advisory Notification of Effluent limits for Swamp and Marsh Waters. The memo includes rationale for the limits.

Mass loading limits for total phosphorus were applied by the assignment of a total maximum daily load (TMDL) to the unnamed tributary discharge stream segment. TMDL is a term that represents the total pollutant a water body can assimilate and still meet water quality standards. The TMDL was developed for total phosphorus due to the low dissolved oxygen impairment (failure to meet water quality standard for dissolved oxygen) for the Norwest River watershed. EPA approved the TMDL April 26, 2011 and SWCB approved the TMDL June 25, 2012. The facility was assigned a waste load allocation (WLA) of an Average annual load of 1187.68 kg/yr and a Maximum daily load of 5.144 kg/day total phosphorus (TP).

I have reviewed the data for all the parameters monitored during the last permit reissuance applicable to this reissuance which include Flow, pH, E.coli,  $CBOD_5$ , TSS, TKN, and DO. The facility was in compliance with all the limits. No changes will be made for this reissuance.

Water quality monitoring was received, 2009, during the last reissuance of this permit. Since Water Quality Standards (WQS) and the design flow of the facility have changed since the last reissuance, another WQS/WLA analysis was performed for this reissuance. Based on the analysis, copper will be monitored due to elevated concentrations. The data collected during this reissuance will allow DEQ to further analyze the need for either continued monitoring or possible limits in order to protect water quality.

Flow: No limit, monthly average and daily maximum monitoring continuous; (Totalizing, Indicating & Recording Equipment). This is a standard requirement for municipal facilities.

<u>pH:</u> 6.0 s.u. minimum, 9.0 s.u. maximum limits, 3 days per week; basis is best professional judgment to protect water quality in the receiving stream.

- CBOD5 and TSS: limited by 10 mg/l (21kg/d) monthly average and 15 mg/l (31kg/d) weekly average; 1 day per week; basis is best professional judgment to protect water quality of the receiving stream. The transition zone between the unnamed tributary and the Northwest River is a swamp and therefore the facility has been assigned "Swamp and Marsh Waters" limits in accordance with memo dated March 9, 1987. There is no evidence of degradation of the receiving stream due to this discharge.
- <u>DO:</u> limited by 3.0 mg/l daily minimum; 3 days per week; basis is best professional judgment to protect water quality in the receiving stream. The transition zone between the unnamed tributary and the Northwest River is a swamp and therefore the facility has been assigned "Swamp and Marsh Waters" limits in accordance with memo dated March 9, 1987. There is no evidence of degradation of the receiving stream due to this discharge.
- $\underline{\textbf{E. coli:}}$  limited by 126 N/CML monthly average; 3 days per week between 10am and 4pm; basis is the Water Quality Standards.
- $\overline{ extbf{tKN:}}$  limited by 3.0 mg/l (6.2kg/d) monthly average and 4.5 mg/l (9.3 kg/d) weekly average; 1 per month; basis is best professional judgment to protect water quality of the receiving stream. The transition zone between the unnamed tributary and the Northwest River is a swamp and therefore the facility has been assigned "Swamp and Marsh Waters" limits in accordance with memo dated March 9, 1987. There is no evidence of degradation of the receiving stream due to this discharge.
- $\overline{ extbf{TP:}}$  limited by 5.14 kg/d maximum; 1 per month; basis is best professional judgment to protect water quality of the receiving stream using mass loadings. Mass loadings are based on TMDL WLA for the receiving stream segment.
- TP Monthly Load: not limited kg/m weekly average; 1 per month; calculation; basis is best professional judgment to protect water quality of the receiving stream using mass loadings. Mass loadings are based on TMDL WLA for the receiving stream segment.
- <u>TP Year-to-Date:</u> not limited kg/yr weekly average; 1 per month; calculation; basis is best professional judgment to protect water quality of the receiving stream using mass loadings. Mass loadings are based on TMDL WLA for the receiving stream segment.
- TP Calendar Year: limited by 1877.68 kg/yr monthly average; 1 per year; calculation; basis is best professional judgment to protect water quality of the receiving stream using mass loadings. Mass loadings are based on TMDL WLA for the receiving stream segment.
- <u>Dissolved Copper:</u> not limited mg/l maximum; 1 per 6 months; basis is best professional judgment to protect water quality of the receiving stream and WQS/WLA analysis.
- Mass Loading  $(kg/d) = Flow (MGD) \times Concentration (mg/l) \times 3.785$

## SECTION IV-C

ATTAGHMENT 1-1

SUBJECT: Advisory Notification of Effluent Limits for Swamp and

Marsh Waters

TO: Larry G. Lawson

FROM: A. J. Anthony

DATE: March 9, 1987

In the event that a proposal is received for discharge to a swamp or marsh that cannot be modeled and the current standards are being violated for whatever reason, OERS recommends the following effluent limits:

Our rationale for these recommendations are as follows:

We have found over the past years, through application of modeling technology to small streams, that the above limits are <u>representative</u> of effluents that are "self-sustaining"; that is: such an effluent will not normally violate the stream standard even if the stream consists of 100% effluent.

Given the fact that the areas of intended application of our recommendations are such that the stream will not possess good mixing process and may in fact contain 100% effluent for significant distances and times render it necessary, in our opinion, that discharges may be essentially of "self-sustaining" quality.

- 2. CBOD, -- We are recommending nitrification and consequently CBOD is what will be measured. In addition, we believe that where both unoxidized nitrogen and hydrocarbons are limited due to considerations of stream dissolved oxygen, it is correct and reasonable to specify them separately to avoid double counting their impacts.
- 3. TSS -- We are recommending that TSS be consistent with the BOD limit. This is consistent with past and current practice and should not be difficult to attain.



- 4. TKN -- We are recommending that unoxidized nitrogen be removed in the treatment plant. The recommended limit on TKN recognizes that a normal domestic effluent usually contains 2-3 mg/l TKN that is refractory and cannot be removed by biological treatment. For industrial discharges this may vary and may be verified by testing. The intent of our recommendation is to remove all biologically oxidizable nitrogen compounds from the effluent.
- 5. DO -- We are recommending that the dissolved oxygen in the effluent be reasonably consistent with that expected to occur in the receiving stream.
- 6. Cl₂ -- Mixing can be expected to be extremely poor or non-existent and the stream can be expected to contain 100% effluent for significant distances and times. In order to ensure that the chlorine standard is not violated, the discharge must meet the standard.

It is our belief that the above limits will be adequate to:

- Protect the beneficial uses of and the aquatic life to be expected in swampy and/or marshy streams.
- Ensure that the limits will not result in additional degradation to the receiving stream.
- 3. Provide consistency with the intent and requirements of the law.

It must be pointed out that the above limits are based on the professional opinions of OERS. They are not the result of the application of any predictive technology. The negotiations and trade-offs normally associated with the application of modeling to identify permit limits are simply not practical in this case for the following reasons:

- There are no models available with which to evaluate various alternatives.
- 2. The recommended limits are based on professional opinion and are therefore not subject to negotiation.
- 3. The recommended limits are very stringent and essentially leave no room for trade-offs among the parameters.

### SECTION IV-C

(ATT 1-3

As is the case with all guidance provided by OERS, the Regions should obtain concurrence from OERS prior to drafting a permit with the above limits. In addition, if the proposed dischargers disagrees with the limits established, then it is our opinion that ample precedent has been established to allow the dischargers to model the system or provide other documentation that the limits as established are not correct subject to the review and approval of the Board.

Please note that toxic requirements are not covered in this memo, and should follow the normal routine for toxics-related issues.

## 2/18/2014 - 10:54 AM

# FRESHWATER WATER QUALITY CRITERIA / WASTELOAD ALLOCATION ANALYSIS

VDOC SBCC Facility Name:

UNTRIB to Indian Creek Receiving Stream:

Permit No.: VA0060526

Version: OWP Guidance Memo 00-2011 (8/24/00)

Stream Information		Stream Flows		Mixing Information		Effluent Information	
Mean Hardness (as CaCO3) =	58.5 mg/L	1Q10 (Annual) ==	0 MGD	Annual - 1Q10 Mix =	100 %	Mean Hardness (as CaCO3) =	114 ma/L
90% Temperature (Annual) =	26 deg C	7Q10 (Annual) =	0 MGD	- 7Q10 Mix =	100 %	90% Temp (Annual) =	25 deg C
90% Temperature (Wet season) =	26 deg C	30Q10 (Annual) =	0 MGD	- 30Q10 Mix =	100 %	90% Temp (Wet season) =	21 deg C
90% Maximum pH =	7.1 SU	1Q10 (Wet season) =	0 MGD	Wet Season - 1Q10 Mix =	100 %	90% Maximum pH =	7.7 SU
10% Maximum pH ==	6.7 SU	30Q10 (Wet season)	0 MGD	- 30Q10 Mix =	100 %	10% Maximum aH =	6.7 SU
Tier Designation (1 or 2) =	· ·	3005 =	0 MGD			Discharae Flow =	0.544 MGD
Public Water Supply (PWS) Y/N? =	>	Harmonic Mean =	0 MGD				
Trout Present Y/N? =	E						
Early Life Stages Present Y/N? =	E						

Parameter	Background		Water Qua	Water Quality Criteria			Wasteload	Wasteload Allocations		Ā	Antidegradation Baseline	in Baseline	-	Ant	Antidegradation Allocations	Allocations			Most Limitin	Most Limiting Allocations	
(ug/l unless noted)	Conc.	Acute	Chronic	Chronic HH (PWS)	Ŧ	Acute	Chronic	HH (PWS)	Ξ	Acute	Chronic HH (PWS)	H (PWS)	Ŧ	Acute	Chronic	HH (PWS)	Ŧ	Acute	Chronic	HH (PWS)	Ŧ
Acenapthene	മ	1	ı	6.7E+02	9.9E+02	1	;	6.7E+02	9.9E+02	ł	1			:		;				6.7E+02	9.9E+02
Acrolein	0	ï	:	6.1E+00	9.3E+00	i	:	6.1E+00	9.3E+00	ŀ	;	:	· · ·	1	ı	ı	;	ı	ľ	6.1E+00	9.3E+00
Acrylonitrile ^c	0	ı	1	5.1E-01	2.5E+00	i	;	5.1E-01	2.5E+00	ı	1	1		ŧ	ï	ı	ı	1	;	5.1E-01	2.5E+00
Aldrin ^c	0	3.0E+00	ı	4.9E-04	5.0E-04	3.0E+00	;	4.9E-04	5.0E-04	ŀ	;	1	1	1	;	1	1	3.0E+00	;	4.9E-04	5.0E-04
(Yearly)	0	1.44E+01	1.82E+00	1	1	1.44E+01 1.82E+00	1.82E+00	;	ı	1	1	;		ı	1	:	;	1 445+04	1 825+00	!	
Ammonia-N (mg/l) (High Flow)	0	1.44E+01	2.36E+00	1	1	1.44E+01 2.36E+00	2.36E+00	ı	1	;	ı	;	i	1	;	:		1.44€+01	2.36E+00	: :	1 1
Anthracene	0	1	ı	8.3E+03	4.0E+04	1	1	8.3E+03	4.0E+04	ı	ŀ	:	:	1	ı	;	;	,	;	8.3E+03	4,0E+04
Antimony	0	1	;	5.6E+00	6.4E+02	1	;	5.6E+00	6.4E+02	1	1	1		ŧ	:	ı	;	;	1	5.6E+00	6.4E+02
Arsenic	0	3.4E+02	1.5E+02	1.0E+01	1	3.4E+02	1.5E+02	1.0E+01	1	1	ı	ı		;	i	ı	ı	3.4E+02	1.5E+02	1.0E+01	ı
Barium	0	;	t	2.0E+03	ı	1	1	2.0E+03	 !	í	:	1		:	ı	:	1	:	1	2.0E+03	:
Benzene ^c	0	ł	;	2.2E+01	5.1E+02	1	ŧ	2.2E+01	5.1E+02	ı	ł	1	1	ı	;	;	;	;	;	2.2E+01	5.1E+02
Benzidine ^c	0	;	1	8.6E-04	2.0E-03	!	:	8.6E-04	2.0E-03	;	;	1	1	1	;	ł		;	:	8.6E-04	2.0E-03
Benzo (a) anthracene ^c	0	1	1	3.8E-02	1.8E-01	ı	ı	3.8E-02	1.8E-01	:	1	;		1	ı	ı	ı	;	ı	3.8E-02	1.8E-01
Benzo (b) fluoranthene ^c	0	:	1	3.8E-02	1.8E-01	1	;	3.8E-02	1.8E-01	;	ı	1	1	ı	;	ł	1	ı	:	3.8E-02	1.8E-01
Benzo (k) fluoranthene ^c	0		1	3.8E-02	1.8E-01	1	1	3.8E-02	1.8E-01	:	;	1	1	1	;	1	1	ı	;	3.8E-02	1.8E-01
Benzo (a) pyrene ^c	0	ı	ı	3.8E-02	1.8E-01	ŀ	ı	3.8E-02	1.8E-01	1	t	1	,	ı	ı	;	1	ı	:	3.8E-02	1.8E-01
Bis2-Chloroethyl Ether ^c	.0	1	ı	3.0E-01	5.3E+00	ı	;	3.0E-01	5.3E+00	1	1	1		;	;	:	1	ı	;	3.05-01	5.3E+00
Bis2-Chloroisopropyl Ether	0	1	1	1.4E+03	6.5E+04	1	ı	1.4E+03	6.5E+04	ı	;	;	1	ı	;	;	1	ı	ı	1.4E+03	6.5E+04
Bis 2-Ethylhexyl Phthalate ^c	0	1	1	1.2E+01	2.2E+01	1	:	1.2E+01	2.2E+01	;	1	1	1	ł	;	ŀ	ı	ï	;	1.2E+01	2.2E+01
Bromoform ^c	0	1	1	4.3E+01	1.4E+03	ı	1	4.3E+01	1.4E+03	1	ı	1	1	ı	;	ŧ	1	1	ì	4.3E+01	1.4E+03
Butylbenzylphthalate	0	1	ı	1.5E+03	1.9E+03	1	ı	1.5E+03	1.9E+03	1	1	;	,	ı	;	ţ	ı	:	1	1.5E+03	1.9E+03
Cadmium	0	4.5E+00	1.3E+00	5.0E+00	ı	4.5E+00	1.3E+00	5.0E+00	1	:	:	1		ł	1	;	1	4.5E+00	1.3E+00	5.0E+00	:
Carbon Tetrachloride ^c	0	ı	ı	2.3E+00	1.6E+01	ı	ı	2.3E+00	1.6E+01	1	1	;	1	ł	1	ı	ŧ	ı	:	2.3E+00	1.6E+01
Chlordane ^c	0	2.4E+00	4.3E-03	8.0E-03	8.1E-03	2.4E+00	4.3E-03	8.0E-03	8.1E-03	:	;	;	1	ı	1	ï	1	2.4E+00	4.3E-03	8.0E-03	8.1E-03
Chloride	0	8.6E+05	2.3E+05	2.5E+05	1	8.6E+05	2.3E+05	2.5E+05	;	t	;	:	;	1	ı	ı	1	8,6E+05	2.3E+05	2.5E+05	1
TRC	0	1.9E+01	1.1E+01	;	1	1.9E+01	1.1E+01	1	I	ı	1	;	;	;	;	:	1	1.9E+01	1.1E+01	ı	ŀ
Chlorobenzene	0	-	;	1.3E+02	1.6E+03	1	-	1.3E+02	1.6E+03	:	1	1		**	:		1	;	ı	1.3E+02	1.6E+03

Parameter	Background		Water Qua	Water Quality Criteria		^	Wasteload Allocations	llocations		An	Antidegradation Baseline	aseline		Antidegra	Antidegradation Allocations	ons	_	Most Limiti	Most Limiting Allocations	
(ng/l unless noted)	Conc.	Acute	Chronic	Chronic HH (PWS)	Ŧ	Acute	Chronic HH (PWS)	H (PWS)	H	Acute	Chronic HH (PWS)	WS) HH	Acute		Chronic HH (PWS)	S) HH	Acute	Chronic	HH (PWS)	Ŧ
Chlorodibromomethane ^c	0	1	1	4.0E+00	1.3E+02	1	1	4.0E+00	1.3E+02		,	:	•		ı	:	ı	:	4.0E+00	1.3E+02
Chloroform	0	1	;	3,4E+02	1.1E+04	1	1	3.4E+02	1.1E+04	;				;	1	ı	ı	·	3.4E+02	1.1E+04
2-Chloronaphthalene	0	1	1	1.0E+03	1.6E+03	;	1	1.0E+03	1.6E+03		1	!			1	1	1	ı	1.0E+03	1.6E+03
2-Chlorophenol	0	1	:	8.1E+01	1.5E+02	i	1	8.1E+01	1.5E+02	;		,		1	1	ı		ı	8.1E+01	1.5E+02
Chlorpyrifos	0	8.3E-02	4.1E-02	i	1	8.3E-02	4.1E-02	1	1	Į	1	;	,		ı	1	8.3E-02	4.1E-02	;	i
Chromium III	0	6.3E+02	8.3E+01	ı	ŧ	6.3E+02	8.3E+01	•	1	ŧ				1	;	;	6.3E+02	8.3E+01	ı	1
Chromium VI	0	1.6E+01	1.1E+01	1	1	1.6E+01	1.1E+01	;	1	i		:	,	:	1	1	1.6E+01	1.1E+01	:	ı
Chromium, Total	0	1	;	1.0E+02	ı	ì	,	1.0E+02	1	1	1	1			1	;		1	1.0E+02	ı
Chrysene ^c	0	1	1	3.8E-03	1.8E-02	1	;	3.8E-03	1.8E-02	ţ		:		1	1	ŧ	:	1	3.8E-03	1.8E-02
Copper	0	1.5E+01	1.0E+01	1.3E+03	;	1.5E+01	1.0E+01	1.3E+03	,	1	1	1		1	ł	;	1.5E+01	1.0E+01	1.3E+03	1
Cyanide, Free	0	2.2E+01	5.2E+00	1.4E+02	1.6E+04	2.2E+01	5.2E+00	1.4E+02	1.6E+04	ı	,	;			1	I	2.2E+01	5.2E+00	1.4E+02	1.6E+04
ووو د مور	0	1	:	3.1E-03	3.1E-03	1	;	3.1E-03	3.1E-03	;	;	;		:	ŧ	:		:	3.1E-03	3.1E-03
ode °	0	ı	ŀ	2.2E-03	2.2E-03	1	ı	2.2E-03	2.2E-03	ı	1	;			i	1	:	1	2.2E-03	2.2E-03
σοτ	0	1.1E+00	1.0E-03	2.2E-03	2.2E-03	1.1E+00	1.0E-03	2.2E-03	2.2E-03	ı	,	;		1	i	;	1.1E+00	1,0E-03	2.2E-03	2.2E-03
Demeton	0	!	1.0E-01	;	1	,	1.0E-01	ı	ı	:	1	1		,	;	l	:	1.0E-01	ı	ı
Diazinon	0	1.7E-01	1.7E-01	:	ı	1.7E-01	1.7E-01	;	1	1	1	1			!	;	1.7E-01	1.7E-01	ŀ	ŧ
Dibenz(a,h)anthracene c	0	ı	ı	3.8E-02	1.8E-01	ı	ŀ	3.8E-02	1.8E-01	;	;	:		;	1	1	;	:	3.8E-02	1.8E-01
1,2-Dichlarobenzene	0	ı	:	4.2E+02	1.3E+03	i	ı	4.2E+02	1.3E+03	ı	ı				1	l		;	4.2E+02	1.3E+03
1,3-Dichlorobenzene	0	1	:	3.2E+02	9.6E+02	t	1	3.2E+02	9.6E+02	:	:			;	:	1	1	1	3.2E+02	9.6E+02
1,4-Dichlorobenzene	0	1	ŀ	6.3E+01	1.9E+02	ı	ı	6.3E+01	1.9E+02	ı	:						1	ı	6.3E+01	1.9E+02
3,3-Dichlorobenzidine ^c	0	ł	;	2.1E-01	2.8E-01	i	:	2.1E-01	2.8E-01	1		1	•		t	:	:	;	2.1E-01	2.8E-01
Dichlorobromomethane c	0	ı	ŀ	5.5E+00	1.7E+02	ŀ	ì	5.5E+00	1.7E+02	ŀ	:	1			;	1	;	1	5.5E+00	1.7E+02
1,2-Dichtoroethane ^c	0	1	ł	3.8E+00	3.7E+02	1	1	3.8E+00	3.7E+02	1	1	;		:	f	1	;	:	3.8E+00	3.7E+02
1,1-Dichloraethylene	0	1	ı	3.3E+02	7.1E+03	ı	ł	3.3E+02	7.1E+03	;	ł	!			1	1	ı	:	3.3E+02	7.1E+03
1,2-trans-dichloroethylene	0	!	;	1.4E+02	1.0E+04	1	1	1,4E+02	1.0E+04	ŀ	1	;			;	•	:	ı	1.4E+02	1.0E+04
2,4-Dichlorophenol	0	1	ı	7.7E+01	2.9E+02	ı	1	7.7E+01	2.9E+02	:	1	1			1	1	:	;	7.7E+01	2.9E+02
2,4-Dichlorophenoxy	0		;	1.0E+02	1	ı	ı	1.0E+02	1	1		:		:	1	;		1	1.0F+02	1
1,2-Dichloropropane ^c	0	!	1	5.0E+00	1.5E+02	:	ı		1.5E+02	:	1	!		;	1	;	;	ı	5.0E+00	1.5E+02
1,3-Dichloropropene ^c	0	ı	1	3.4E+00	2.1E+02	ı	ŀ		2.1E+02	ı	1	:		;	1	;	:	:	3.4E+00	2.1E+02
Dieldrin ^c	0	2.4E-01	5.6E-02	5.2E-04	5,4E-04	2.4E-01	5.6E-02		5.4E-04	1	ŧ	!		,	;	ı	2.4E-01	5.6E-02	5.2E-04	5,4E-04
Diethyl Phthalate	0	!	1	1.7E+04	4.4E+04	ı	ı	1.7E+04	4.4E+04	1	1	:		;	1	1		1	1.7E+04	4.4E+04
2,4-Dimethylphenol	0	1	ı	3.8E+02	8.5E+02	:	;	3.8E+02	8.5E+02	;	1	!		,		i	:	1	3.8E+02	8.5E+02
Dimethyl Phthalate	0	;	1	2.7E+05	1.1E+06	i	1	2.7E+05	1.1E+06	:		!		;	1	1	1	1	2.7E+05	1.1E+06
Di-n-Butyl Phthalate	0	ı	ı	2.0E+03	4.5E+03	ı	ì	2.0E+03	4.5E+03	1	;	1		;	1	1	1	:	2.0E+03	4.5E+03
2,4 Dinitrophenol	0	1	1	6.9E+01	5,3E+03	1	ł	6.9E+01	5.3E+03	1	. 1			•	ţ	ı	1	:	6.9E+01	5.3E+03
2-Methyl-4,6-Dinitrophenol	0	1	1	1.3E+01	2.8E+02	1	ï	1.3E+01	2.8E+02	ı	;	1		;	1	1	:	;	1.3E+01	2.8E+02
2,4-Dinitrotoluene ^c	0	ı	ì	1.1E+00	3.4E+01	;	ŀ	1.1E+00	3.4E+01	ĭ	:	1		•	1	1	1	:	1.15+00	3.4E+01
tetrachlorodibenzo-p-dioxin	0	1	;	5.0E-08	5.1E-08	t	ı	5.0E-08	5.1E-08	;	ı	;		1	ı	:		:	5.0E-08	5.1E-08
1,2-Diphenylhydrazine ^c	0	1	1	3.6E-01	2.0E+00	ı	1	3.6E-01	2.0E+00	ì	ţ	:		i !	1	,	!	ı	3.6E-01	2.0E+00
Alpha-Endosulfan	0	2.2E-01	5.6E-02	6.2E+01	8.9E+01	2.2E-01	5.6E-02	6.2E+01	8.9E+01	I	1	1		•	t	ı	2.2E-01	5.6E-02	6.2E+01	8.9E+01
Beta-Endosulfan	0	2.2E-01	5.6E-02	6.2E+01	8.9E+01	2.2E-01	5.6E-02	6.2E+01	8.9E+01	1	1	!		,	1	;	2.2E-01	5.6E-02	6.2E+01	8.9E+01
Alpha + Beta Endosulfan	0	2.2E-01	5.6E-02	:	1	2.2E-01	5.6E-02	:	:	ı				,	ı	;	2.2E-01	5.6E-02	ı	1
Endosulfan Sulfate	0	1	ı	6.2E+01	8.9E+01	1	i	6.2E+01	8.9E+01	ŀ	ı	;		,	1	!	ı	:	6.2E+01	8.9E+01
Endrin	0	8.6E-02	3.6E-02	5.9E-02	6.0E-02	8.6E-02	3.6E-02	5.9E-02	6.0E-02	:	1	I		•	;	ŧ	8.6E-02	3.6E-02	5.9E-02	6.0E-02
Endrin Aldehyde	0	-	:	2.9E-01	3.0E-01	-	-	2.9E-01	3.0E-01		1	:		;	:	:	1	:	2.9E-01	3.0E-01

Parameter	Background		Water Qu	Water Quality Criteria			Wasteload Allocations	Allocations	-	Ar	Antidegradation Baseline	n Baseline		Anti	Antidegradation Allocations	flocations		Ž	ost Limiting	Most Limiting Allocations	
(ug/l unless noted)	Conc.	Acute	Chronic	Chronic HH (PWS)	H	Acute	Chronic HH (PWS)	HH (PWS)	Ħ	Acute	Chronic H	HH (PWS)	Ŧ	Acute	Chronic HH (PWS)	(PWS)	표	Acute	Chronic	HH (PWS)	圭
Ethylbenzene	0	;	1	5.3E+02	2.1E+03	;	1	5.3E+02	2.1E+03	;	1	1	1	,			-	:	-{	5.3E+02	2.1E+03
Fluoranthene	0	;	1	1.3E+02	1.4E+02	1	;	1.3E+02	1.4E+02	ŀ	1	ŧ	1	ı	. 1	;	1	ı	;	1.3E+02	1.4E+02
Fluorene	0	1	1	1.1E+03	5.3E+03	;	;	1.1E+03	5.3E+03	ı	1	1	1	ŀ	1	ŀ	!	:	:	1.1E+03	5.3E+03
Foaming Agents	0	ı	;	5.0E+02	;	1	i	5.0E+02	1	ì	ı	ı		ŀ	:	ı	1	ı	1	5.0E+02	1
Guthion	0	ı	1.0E-02		i	:	1.0E-02	ı	1	;	1	1		ì	ł	;	1	1	1.0E-02	;	ı
Heptachlor C	0	5.2E-01	3.8E-03			5.2E-01	3.8E-03	7.9E-04	7.9E-04	ı	1	:	ŀ	ı	1	ı	<b>-</b>	5.2E-01	3.8E-03	7.9E-04	7.9E-04
Heptachlor Epoxide ^c	0	5.2E-01	3.8E-03			5.2E-01	3.8E-03	3.9E-04	3.9E-04	ŀ	ı	;		;	1	;	;	5.2E-01	3.8E-03	3.9E-04	3.9E-04
Hexachlorobenzenec	0	;	1	2.8E-03		1	1		2.9E-03	1	1	ŀ		ł	I	;	1	:	1	2.8E-03	2.9E-03
Hexachlorobutadiene	0	;	1	4,4E+00	1.8E+02	ı	1	4.4E+00	1.8E+02	ŀ	ţ	·	1	ı	;	ı	;	,	1	4.4E+00	1.8E+02
Hexachlorocyclohexane Alpha-BHC ^c	0	ı	ı	2 6F-02	4 9F-02	1	:	2 GE-02	4 9E-02	;	1	i								i L	
Hexachlorocyclohexane	•			10.11		ı				:	:	ŧ		ł	ì	:	:	:	:	Z.6E-0Z	4.9E-02
Beta-BHC ^c	0	;	t	9.1E-02	1.7E-01	1	1	9.1E-02	1.7E-01	;	1	ı	1	ı	ı	ı	1	:	1	9.1E-02	1.7E-01
Hexachlorocyclohexane				!																	
Gamma-BHC (Lindane)	0	9.5E-01	ŧ	9.8E-01	1.8E+00	9.5E-01	1		1.8E+00	;	1	1		ŀ	1	:	1	9.5E-01	:	9.8E-01	1.8E+00
Hexachlorocyclopentadiene	0	:	1	4.0E+01	1,1E+03	;	ŧ	4.0E+01	1.1E+03	;	ı	:	1	;	1	;	1	:	1	4.0E+01	1.1E+03
Hexachloroethane ^c	0	i	:	1,4E+01	3,35+01	1	ı	1.4E+01	3.3E+01	t	;	1	1	1	:	1	۱	;	ı	1.4E+01	3.3E+01
Hydrogen Sulfide	0	ŀ	2.0E+00		:	;	2.0E+00	1		;	. 1	1	1	;	ŀ	ŧ	:	1	2.0E+00	1	1
Indeno (1,2,3-cd) pyrene ^c	0	ł	;	3.8E-02	1.8E-01	1	ı	3.8E-02	1.8E-01	1	ı	1		;	1	;	1	;	ı	3.8E-02	1.8E-01
lron	0	ı	1	3.0E+02	;	1	:	3.0E+02	·····	;	ı	ı		1	1	ł	;	:	;	3.0E+02	:
(sophorone ^c	0	ı	1	3.5E+02	9.6E+03	1	ı	3,5E+02	9.6E+03	ł	:	1		;	:	;	:	;	ı	3.5E+02	9.6E+03
Kepone	0	1	0.0E+00	-	ł	<b>;</b>	0.0E+00	:	1	1	:	:	:	1	;	ì	1	:	0.0E+00	1	
Lead	0	1.4E+02	1.6E+01	1.5E+01	1	1.4E+02	1.6E+01	1.5E+01		;	ł	:		:	ı	1	-	1.4E+02	1.6E+01	1.5E+01	;
Malathion	0	ŀ	1.0E-01	1	ı	1	1.0E-01	ı	;	ŧ	ı	ì	· ·	1	:	1	:	1	1.0E-01	;	1
Manganese	0	ı	1	5.0E+01	:	ı	ı	5.0E+01	1	ı	ı	1	ı	ı	ŧ	1	ı	ı	1	5.0E+01	1
Mercury	0	1,4E+00	7.7E-01		;	1.4E+00	7.7E-01	:	;	ı	1	1		ı	:	1		1.4E+00	7.7E-01	;	;
Methyl Bromide	0	ı	ı	4.7E+01	1.5E+03	1	1	4.7E+01	1.5E+03	1	ı	1	1	ŧ	ı	:		ı	:	4.7E+01	1.5E+03
Methylene Chloride ^c	0	ŀ	:	4.6E+01	5.9E+03	1	;	4.6E+01	5.9E+03	1	ı	ı	I	ŀ	ı	1		1	ı	4.6E+01	5.9E+03
Methoxychlor	0	ł	3.0E-02	1.0E+02	ı	1	3.0E-02	1.0E+02	1	t	ı	ı		;	ì	1		1	3.0E-02	1.0E+02	ı
Mirex	0	;	0.0E+00		1	I	0.0E+00	ı	ì	ı	1	ı		ì	1	1	1	1	0.0E+00	1	1
Nickel	0	2.0E+02	2,3E+01	1 6.1E+02	4.6E+03	2.0E+02	2.3E+01	6.1E+02	4.6E+03	ŀ	t	;		ı	i	;	1	2.0E+02	2.3E+01	6.1E+02	4.6E+03
Nitrate (as N)	0	;	:	1.0E+04	ŧ	;	ł	1.0E+04	1	ı	ı	ı	1	ı	1	1	;	:	;	1.0E+04	1
Nitrobenzene	0	ı	1	1.7E+01	6.9E+02	1	i	1.7E+01	6.9E+02	1	1	ı		ŀ	ı	:	;	:	i	1.7E+01	6.9E+02
N-Nitrosodimethylamine	0	1	1	6.9E-03	3.0E+01	;	ŀ		3.0E+01	1	ı	1	;	:	;	;		;	;	6.9E-03	3.0E+01
N-Nitrosodiphenylamine	0	ı	1	3.3E+01	6.0E+01	1	ı		6.0E+01	1	:	1		1	1	ı	1	:	;	3.3E+01	6.0E+01
N-Nitrosodi-n-propylamine	0	1	1	5.0E-02	5.1E+00	1	ŀ	5.0E-02	5.1E+00	ı	t	ı	ı	;	1	1		:	:	5.0E-02	5.1E+00
Nonylphenol	0	2.8E+01	6.6E+00	1	ı	2.8E+01	6.6E+00	1	1	;	1	;	<u> </u>	ı	ı	1	1	2.8E+01 6	6.6E+00	ı	1
Parathion	0	6,5E-02	1.3E-02		1	6.5E-02	1,3E-02	;	;	:	;		1	1	1	1	-	6.5E-02	1.3E-02	;	ı
PCB Total	0	ı	1.4E-02			1	1.4E-02		6.4E-04	ı	;	ı	1	1	!	1	1	:	1.4E-02	6.4E-04	6.4E-04
Pentachlorophenol >	0	6.5E+00	5.0E+00	0 2.7E+00	3.0E+01	6.5E+00	5.0E+00	2.7E+00	3.0E+01	;	1	:	1	1	;	1	1	6.5E+00 £	5.0E+00	2.7E+00	3.0E+01
Phenol	•	1	1	1.0E+04	8.6E+05	,	1		8.6E+05	ŀ	,	ŧ	1	ı	1	:	;	ı	;	1.0E+04	8.6E+05
Pyrene	0	1	1	8.3E+02	4.0E+03	1	ļ	8.3E+02	4.0E+03	ı	:	i		1	;	:	1	1	ı	8.3E+02	4.0E+03
Radionuclides Gross Alpha Activity	0	:	1	1	1	1	:	ı	ı	1	ŀ	ţ	;	i	i	:	1	ı	ı	ı	ı
(pCi/L)	0	1	1	1.5E+01	ı	1	;	1.5E+01	ı	ı	ŧ	ı	1	ı	:	:	1	i	1	1.5E+01	1
(mrem/yr)	0	:	1	4.0E+00	1		1	4 0F+00	1	:	;	;		i			***************************************			0	
Radium 226 + 228 (pCi/L.)	0	;	,	5.0E+00			: :	20.170.72	1 1	: :	: ;	<b>!</b> ;	1 :	:	:		1	1	ł	4.0E+00	ı
Uranium (uq/l)	, с	;	:	3.014.01				3.05.00		t ;	:	ı		1	;	ı	ı	ı	ı	5.05+00	:
								10.70					1			1	-		-	3.0=+01	:

Parameter	Background		Water Quality Criteria	lity Criteria			Wasteload Allocations	Allocations		Ä	ntidegradati	Antidegradation Baseline		Anti	degradation	Antidegradation Allocations	-	-	Aost Limitin	Most Limiting Allocations	
(ug/l unless noted)	Conc.	Acute	Chronic	Chronic HH (PWS)	Ŧ	Acute	Chronic	ic HH (PWS)	Ŧ	Acute	Chronic	(SMd) HH	王	Acute	Chronic HH (PWS)	IH (PWS)	Ŧ	Acute	Chronic	HH (PWS)	壬
Selenium, Total Recoverable	0	2.0E+01	5.0E+00	5.0E+00 1.7E+02	4.2E+03	2.0E+01	5.0E+00	1.7E+02	4.2E+03	ı		ŀ	1	1	:	-	-	2.0E+01	5.0E+00	1.7E+02	4.2E+03
Silver	0	4.3E+00	:	ı	ı	4.3E+00	1	1	ı	;	ı	,	ŧ	;	;	:	1	4.3E+00	;	:	1
Sulfate	0	1	ï	2.5E+05	1	1	:	2.5E+05	1	i	:	1	,	1	i	i	1	:	;	2.5E+05	ı
1,1,2,2-Tetrachloroethane ^c	0	;	1	1.7E+00	4.0E+01	ı	:	1.7E+00	4.0E+01	1	ı	1	;	1	ı	ŧ	1	ı	ı	1.7E+00	4.0E+01
Tetrachloroethylene ^c	0	1	;	6.9E+00	3.3E+01	í	;	6.9E+00	3.3E+01	ı	;	1	:	1	ŀ	ŧ	;	;	ı	6.9E+00	3.3E+01
Thallium	0	1	1	2.4E-01	4.7E-01	;	1	2.4E-01	4.7E-01	ı	1	,i	:	1	1	ŧ	1	ı	ŧ	2.4E-01	4.7E-01
Toluene	0	!	1	5.1E+02	6.0E+03	ŧ	ı	5.1E+02	6.0E+03	:	ı	1	;	ı	ł	ì	;	:	ı	5.1E+02	6.0E+03
Total dissolved solids	0	1	1	5.0E+05	ı	1	1	5.0E+05	ı	1	1	;	1	1	;	ı	;	:	t	5.0E+05	:
Toxaphene ^c	0	7.3E-01	2.0E-04	2.8E-03	2.8E-03	7.3E-01	2.0E-04	2.8E-03	2.8E-03	;	ţ	1	1	1	1	ŧ	1	7.3E-01	2.0E-04	2.8E-03	2.8E-03
Tributyltin	0	4.6E-01	7.2E-02	ı	,	4.6E-01	7.2E-02	i	ı	ı	;	,	1		1	ı	1	4.6E-01	7.2E-02	:	1
1,2,4-Trichlorobenzene	0	;	ı	3.5E+01	7.0E+01	1	1	3.5E+01	7.0E+01	:	1	ı	1	;	ł	ı	:	;	ı	3.5E+01	7.0E+01
1,1,2-Trichloroethane ^c	0	,	ŧ	5.9E+00	1.6E+02	;	1	5.9E+00	1.6E+02	ı	1	ļ	1	;	ı	;	;	:	;	5.9E+00	1.6E+02
Trichloroethylene ^c	0	;	:	2.5E+01	3.0€+02	1	1	2.5E+01	3.0E+02	ŀ	ı	ı	1	ı	1	ı	1	ı	;	2.5E+01	3.0E+02
2,4,6-Trichlorophenol ^c	0	1	;	1,4E+01	2.4E+01	:	ŀ	1.4E+01	2.4E+01	,	1	:	1	ł	1	1	1	ı	;	1.4E+01	2.4E+01
2-(2,4,5-Trichlorophenoxy) propionic acid (Silvex)	0	ı	,	5.0E+01	1	i	ţ	5.0E+01	ı	:	1	ì	I	1	ı	;	1	i	ı	5.05+01	:
Vinyl Chloride ^c	0	1	;	2.5E-01	2.4E+01	1	1	2.5E-01	2.4E+01	1	ı	:	:	;	;	;	:	:	1	2.5E-01	2.4E+01
Zinc	٥	1.3E+02		1.3E+02 7.4E+03 2.6E+04 1.3E+02 1.3E+02	2.6E+04	1.3E+02	1	7.4E+03	2.6E+04	1	ļ	:	1	1	ı	:	;	1.3E+02	1.3E+02	7.4E+03	2.6E+04

	:	,	
	5	9	
	5	į	
		ž	
٠	•	Ξ	

1. All concentrations expressed as micrograms/liter (ug/l), unless noted otherwise

2. Discharge flow is highest monthly average or Form 2C maximum for Industries and design flow for Municipals

3. Metals measured as Dissolved, unless specified otherwise

4. "C" indicates a carcinogenic parameter

5. Regular WLAs are mass balances (minus background concentration) using the % of stream flow entered above under Mixing Information.

Antidegradation WLAs are based upon a complete mix.

6. Antideg. Baseline = (0.25(WQC - background conc.) + background conc.) for acute and chronic

= (0.1(WQC - background conc.) + background conc.) for human health

Harmonic Mean for Carcinogens. To apply mixing ratios from a model set the stream flow equal to (mixing ratio - 1), effluent flow equal to 1 and 100% mix. 7. WLAs established at the following stream flows: 1Q10 for Acute, 3QQ10 for Chronic Ammonia, 7Q10 for Other Chronic, 3QQ5 for Non-carcinogens and

Metal	Target Value (SSTV)	Note: do not use QL's lower than the
Antimony	5.6E+00	minimum QL's provided in agency
Arsenic	1.0E+01	guidance
Barium	2.0E+03	
Cadmium	7.5E-01	
Chromium III	5.0E+01	-
Chromium VI	6.4E+00	
Соррег	6.0E+00	
Iron	3.0E+02	
Lead	9.6E+00	
Manganese	5.0E+01	
Mercury	4.6E-01	
Nickel	1.4E+01	
Selenium	3.0E+00	
Silver	1.7E+00	
Zinc	5.2E+01	

### ATTACHMENT 7 SPECIAL CONDITIONS RATIONALE

### VPDES PERMIT PROGRAM LIST OF SPECIAL CONDITIONS RATIONALE

Name of Condition:

- B. OTHER REQUIREMENTS OR SPECIAL CONDITIONS
- 1.a. Sludge Reopener

Rationale: Required by the VPDES Permit Regulation, 9 VAC 25-31-220 C., and  $\overline{40}$  CFR 122.44 (c)(4), which note that all permits for domestic sewage treatment plants (including sludge-only facilities) include any applicable standard for sewage sludge use or disposal promulgated under Section 405(d) of the Clean Water Act.

1.b. Water Quality Standards Reopener

 $\overline{\text{Rationale}}$ : The VPDES Permit Regulation, 9 VAC 25-31-220 D requires effluent limitations to be established which will contribute to the attainment or maintenance of water quality criteria.

1.c. Total Maximum Daily Load (TMDL) Reopener

Rationale: For specified waters, Section 303(d) of the Clean Water Act requires the development of total maximum daily loads necessary to achieve the applicable water quality standards. The TMDL must take into account seasonal variations and a margin of safety. In addition, Section 62.1-44.19:7 of the State Water Control Law requires the development and implementation of plans to address impaired waters, including TMDLs. This condition allows for the permit to be either modified or, alternatively, revoked and reissued incorporating the requirements of a TMDL once it is developed. In addition, the reopener recognizes that, in according to Section 402(o)(1) of the Clean Water Act, limits and/or conditions may be either more or less stringent than those contained in this permit. Specifically, they can be relaxed if they are the result of a TMDL, basin plan or other wasteload allocation prepared under Section 303 of the Act.

2. Licensed Operator Requirement

Rationale: The Permit Regulation, 9 VAC 25-31-200 D and Code of Virginia 54.1-2300 et. seq., Rules and Regulations for Waterworks and Wastewater Works Operators (18 VAC 160-20-10 et seq.) requires licensure of operators.

3. Reliability Class

<u>Rationale</u>: Required by Sewage Collection and Treatment Regulations, 12 VAC 5-581-20 and 120 for all municipal facilities.

4. CTC, CTO and O & M Manual Requirements

Rationale: Required by the State Water Control Law, Section 62.1-44.19; the Sewage Collection and Treatment Regulations (12 VAC 5-581 et seq); Section 401 of the Clean Water Act; 40 CFR 122.41(e); and the VPDES Permit Regulation (9 VAC-25-31-190E).

5. 95% Design Capacity Notification

Rationale: Required by the VPDES Permit Regulation, 9 VAC 25-31-200 B.2. for all POTW and PVOTW permits. Best professional judgment is used to apply this condition to other (private) municipal treatment facilities.

6. Quantification Levels Under Part I.A.

Rationale: States are authorized to establish monitoring methods and procedures to compile and analyze data on water quality, as per 40 CFR part 130, Water Quality Planning and Management, subpart 130.4. Section b. of the special condition defines QL and is included per BPJ to clarify the difference between OL and MDL.

7. Compliance Reporting Under Part I.A.

Rationale: Defines reporting requirements for toxic parameters and some conventional parameters with quantification levels to ensure consistent, accurate reporting on submitted reports.

8. Effluent Monitoring Frequencies

Rationale: The incentive for reduced monitoring is an effort to reduce the cost of environmental compliance and to provide incentives to facilities which demonstrate outstanding performance and consistent compliance with their permits. Facilities which cannot comply with specific effluent parameters or have other related violations will not be eligible for this benefit. This is in conformance with Guidance Memorandum No. 98-2005 - Reduced Monitoring and EPA's proposed "Interim Guidance For Performance-Based Reduction of NPDES Permit Monitoring Frequencies" (EPA 833-B-96-001) published in April 1996.

9. Nutrient Reporting Calculations

Rationale: \$62.1-44.19:13 of the Code of Virginia defines how annual nutrient loads are to be calculated. The TMDL WLA for this facility as assigned is not in the form of a concentration limit (mg/l) as defined in the above statute but rather in a mass load (kg/d) and therefore the conversion from concentration limit to mass load part of the calculation is not required in order to demonstrate compliance with the WLA as required by the TMDL.

10. Indirect Dischargers

Rationale: Required by VPDES Permit Regulation, 9 VAC 25-31-200 B.1. for POTWs and PVOTWs that receive waste from someone other than the owner of the treatment works.

11. Sludge Management Plan

Rationale: The VPDES Permit Regulation, 9 VAC 25-31-420, and 40 CFR 503.1 specify the purpose and applicability for sludge management plans. The VPDES Permit Regulation, 9 VAC 25-31-100 J.4., also sets forth certain detailed information which must be included in a sludge management plan. The VPDES sewage sludge permit application form and its attachments constitute the sludge management plan and will be considered for approval with the VPDES permit. In addition, the Biosolids Use Regulation, 12 VAC 5-585-330 and 340, specifies the general purpose and control requirements for an O&M manual in order to facilitate proper O&M of the facilities to meet the requirements of the regulation.

### ATTACHMENT 8

RECEIVING WATERS INFO./
TIER DETERMINATION/STORET DATA/
STREAM MODELING/
303(d) LISTED SEGMENTS

### Planning Permit Review

Date: 1/2/2014

To: Kristie Britt, TRO

Permit Writer: MYW

Facility: VDOC St. Brides Correctional Center

Permit Number: VA0060526

Issuance, Reissuance or Modification (if Modification describe): Reissuance

Permit Expiration Date: 4/2/2014

Waterbody ID (ex: VAT-G15E): VAT-K40R

Topo Name: Moyock

Facility Address:

701 Sanderson Road, Chesapeake, VA 23328

Receiving Stream: Attached are topographic maps showing facility property boundaries and outfall(s) locations for those included in this request.

meradod m ums request.			
Stream Name: Unnamed Tributary to Ind	ian Creek		
Stream Data Requested?			
Outfall #: 001	Lat Lon: 36° 36' 41" 076° 11' 3"		
Outfall #:	Lat Lon:		
Outfall #:	Lat Lon:		
Stream Name (2):			
Stream Data Requested?			
Outfall #:	Lat Lon:		
Outfall #:	Lat Lon:		
Outfall #:	Lat Lon:		

If greater than 2 receiving streams or 3 outfalls per stream please provide a separate table with outfall listings and Latitude Longitude description.

### Planning Review:

303 (d): Indica	ate Outfalls which discharge direc	tly to an impaired
	tream segment and parameters in	
Outfall 001 does	not directly discharge to an impaired s	egment. The UT eventually discharges to Indian Creek that is impaired for
DO.		
Tier Determin	ation	
Tier	The Outfall discharges to a Tie	er 1 water. The UT to Indian Creek is a low flow stream. See Attachment 1.
Tier		
Management 1	Plan	
Is the facility Re	ferenced in a Management Plan?	No
Are limits contai	ned in a Management Plan?	No

Review will be completed in 30 days of receipt of request.

### **Additional Comments:**

KNB 1/14/2014			

Until further guidance is provided by OWRM Permits, assessment of waters for NH₃ should be based upon OWRM Guidance No. 93-015 from Larry G. Lawson, dated June 22, 1993.

The above guidance specifies that the ambient NH₃ data should be compared to the NH₃ standard (calculated using 90th percentile of ambient data for pH and temperature of that segment) and by using the "STANDARDS.EXE Program" developed by OWRM Permits Modelling. (These environmental conditions are considered critical design conditions to protect water quality and to comply with WQS.) If the 97th percentile of the in-stream data is greater than either of the calculated NH₃ standards (chronic or acute), then OWRM considers the standard is being violated and the segment is WQL.

### 2.4.7 Wasteload Allocations Where The 7010 Is Zero Or Minimal

A discharge to a water course with a 7Q10 of zero or near zero would be required to have effluent limits that would comply with water quality standards, at a minimum. The discharge would have to be "self sustaining" so to comply with water quality standards. Therefore, the discharge would be WQL and the receiving water course with a 7Q10 of zero near zero would be considered a tier 1 segment.

A discharge to a tier 1 water that empties into a tier 2 water would have to be evaluated for antidegradation at the point of confluence of the two water courses, if the discharge is in close enough proximity to impact the tier 2 water. In the above scenario, antidegradation requirements to protect tier 2 waters may apply to a discharge to a tier 1 water. Therefore, effluent limits may be more stringent than required by the numerical water quality standards.

If a discharge occurs to a dry ditch or tributary that empties into a free flowing stream and the distance from the discharge to the next confluence is too short to model (based upon the current modelling programs), then the discharge should be modelled as if it occurs directly to the free flowing stream.

### 2.4.8 Estuaries - Wasteload Allocations & TMDL Development

Similar to freshwater streams, water quality wasteload allocations (WQWLAs) and TMDLs in all tidal influenced waters will be expressed as a mass limitation for the conventional parameters (BOD $_5$ , cBOD $_5$ , TKN, and NH $_3$ ) and as a concentration for toxics.

Tidal freshwater segments and transition zone segments identified

Draft 3/04/94 Attachment I-1
TIEF LJUSTIFICATION for Low Flow Streams.

Dry-Lit

### DEPARTMENT OF ENVIRONMENTAL QUALITY

WATER DIVISION

OFFICE OF WATER RESOURCE MANAGEMENT

(SECOND DRAFT)

GUIDANCE MANUAL

FOR THE

VIRGINIA WATER QUALITY MANAGEMENT PLAN

March 4, 1994

### **TMDL Permit Review**

Date: 1/2/2014

To: Jennifer Howell, TRO

√JSH 1/10/2014

Permit Writer: MYW

Facility: VDOC St. Brides Correctional Center

Permit Number: VA0060526

Issuance, Reissuance or Modification (if Modification describe): Reissuance

**Permit Expiration Date: 4/2/2014** 

Waterbody ID (ex: VAT-G15E): VAT-K40R

Topo Name: Moyock

Facility Address:

701 Sanderson Road, Chesapeake, VA 23328

**Receiving Stream:** Attached are topographic maps showing facility property boundaries and outfall(s) locations for those included in this request.

Stream Name: Unnamed Tributary to Indian Co	reek
Click here to enter text.	
Outfall #: 001	Lat Lon: 36° 36' 41" 076° 11' 3'
Outfall #: Click here to enter text.	Lat Lon: Click here to enter text.
Outfall #: Click here to enter text.	Lat Lon: Click here to enter text.
Stream Name (2): Click here to enter text.	
Click here to enter text.	
Outfall #: Click here to enter text.	Lat Lon: Click here to enter text.
Outfall #: Click here to enter text.	Lat Lon: Click here to enter text.
Outfall #: Click here to enter text.	Lat Lon: Click here to enter text.

If greater than 2 receiving streams or 3 outfalls per stream please provide a separate table with outfall listings and Latitude Longitude description.

Is there a design flow change? If yes give the change. Click here to enter text.

### **TMDL Review:**

Is a TMDL IN PROGRESS for the receiving stream? No	
Has a TMDL been APPROVED that includes the receiving stre	eam?
Yes, see below	
If yes, Include TMDL Name, Pollutant(s) and date of approva	al:
Total maximum daily load development for the Northwest River waters	hed: a total phosphorus TMDL due to low dissolved oxygen
impairment: Total phosphorus: EPA approved 4/26/2011, SWCB approved 4/2	roved 6/25/2012.
Is the facility assigned a WLA from the TMDL?	Yes, see below
If Yes, what is the WLA?	
Average annual load = 1877.68 kg/yr Total phosphorus	
Maximum daily load = 5.144 kg/day	
1	

Review will be completed in 30 days of receipt of request.

### **Additional Comments:**

### TMDL Permit Review

Loads are calculated using the design flow provided during TMDL development (0.544 mil gal/ day)

### ATTACHMENT 9

TABLE III(a) AND TABLE III(b) - CHANGE SHEETS

TABLE III(à)

## VPDES PERMIT PROGRAM Permit Processing Change Sheet

Effluent Limits and Monitoring Schedule: (List any changes FROM PREVIOUS PERMIT and give a brief rationale for the changes). . H

OUTFALL NUMBER	PARAMETER CHANGED	MONITORING LIMITS CHANGED FROM / TO	EFFLUENT LIMITS CHANGED FROM / TO	RATIONALE	DATE & INITIAL
001	<b>라</b>	None to 1/Month	None to maximum 5.14 kg/d	Requirement from Northwest River TMDL	1/30/14 MYW
001	TP Monthly Load	None to 1/Month	Calculated kg/m	Requirement from Northwest River TMDL	1/30/14 MYW
001	TP Year-to- date	None to 1/Month	Calculated kg/yr	Requirement from Northwest River TMDL	1/30/14 MYW
001	TP Calendar Year	None to 1/Year	Monthly Average 1187.68 kg/yr	Requirement from Northwest River TMDL	1/30/14 MYW
001	Dissolve Copper	None to 1/6 Months	Monitoring only, maximum	BPJ based on WQS/WLA analysis	02/18/14 MYW

OTHER CHANGES FROM:	CHANGED TO:	DATE & INITIAL
		1/30/14
Special Condition	Add B.9 Nutrient Reporting Calculation	MXM
		1/30/14
EPA Checklist	No longer required for fact sheet	MXW
No TMDL requirement	TMDL for TP see Attachment 8 - discharge to a	1/30/14
	303(d) listed segment	MXM

ATTACHMENT 10

CHRONOLOGY SHEET

### Chronology of Events 1/31/2014

N	PID VA0060526	Facility Name VDOC - St Brides Correctional Co	enter Activi	ty Reissuance
	Code	Event	Date	Comment
1	316A	316(a) Variance		
2	APRD	Application received at RO 1st time	08/15/2013	
3	DTOWNC3	Third time comments received from owner		
4	DTOBJ1	First time comments received from owner on draft		
5	DTOWN1	FS/SOB draft permit sent to owner		
6	DTEPA	FS/SOB draft permit sent to EPA/OWPS		
7	MISC	Miscellaneous		
8	LGNPERM	Local gov't notification		
9	DTOWN3	FS/SOB draft permit sent to owner 3rd time		
10	ROAPCP	Application Administratively complete	11/22/2013	
11	DTSITE	Site visit		
12	APCP	Application totally / technically complete	12/12/2013	
13	VPDESNO	Permit number obtained (Iss)		
14	DTMIF	App sent to Fed Agencies (list in comment field)		
15	APRET3	App returned/Additional info requested 3rd time		
16	RONOTE	Riparian landowners notified (Iss,Mod)		
17	FAMSUB	Financial Assurance Mechanism Submitted		
18	APRPHOCAL2	Second Application Reminder Phone Call	08/05/2013	
19	FLED	Permit expires		
20	DTEFF	Permit effective		
21	PN2CO	PN sent to CO for mailing list web site distrib		
22	DTOWNC2	Second time comments received from owner		
23	DTOWN2	FS/SOB draft permit sent to owner 2nd time		
24	DT1VIMS	VMRC concurrence on draft permit		
25	DTSITERP	Site inspection report	02/12/2010	
26	DT1VDH	App sent to State Agencies (list in comment field)	11/27/2013	
27	APRD4	Applic/Additional info received at RO 4th time		
28	APRET2	App returned/Additional info requested 2nd time		
29	APRPHOCAL1	First Application Reminder Phone Call	06/10/2013	due on 6/6 but I was out on SD
30	APCOMLET	App complete letter sent to permittee	12/13/2013	
31	PNHEAR	Public hearing date		
32	DTC2EPA	EPA concurrence on draft permit		
na wood	APRET4	App returned/Additional info requested 4th time		
34	DTLP	Reissuance letter mailed	04/01/2013	email
35	PREVFLED	Old expiration date	04/02/2014	
	DT1PLAN	FS/SOB draft permit sent to planning		
37	APRET1	App returned/Additional info requested 1st time		
	APDU	Reissuance application due	10/04/2013	
	DTDMRDUE	First DMR due		
	DTOWNC4	Owner concurrence of draft permit		
	DTPLAN	Planning concurrence on draft permit		
	DTC1VDH	Comments rec'vd from State Agencies on App	12/05/2013	VDH, No comments from DSS
	APRD2	Applic/Additional Info received at RO 2nd time		<b>,</b>

N	PID VA0060526	Facility Name VDOC - St Brides Correctional Cent	ter Activit	y Reissuance
	Code	Event	Date	Comment
44	SCCERTR	State Corporation certification received		
45	PNOT	Date of Public Notice		
46	DTNEWS	Public notice letter sent to newspaper		
47	DTPNAUT	Public notice authorization received from owner	08/15/2013	
48	DTADJ	FS/SOB/draft permit sent to adj. State(s)		
49	DTPKVDH	FS/SOB draft permit sent to State Agencies (list i		
50	DTCOE	Comments rec'vd from Federal Agencies on App		
51	APRD3	Applic/Additional info received at RO 3rd time		
52	ROLISTR	Riparian owner list received		
53	RORTTC	Riparian owner request sent to tax commissioner		
54	DEPFEE	Application fee deposited		
55	DTSIGN	Date Permit signed		
56	DTC2VDH	VDH concurrence on draft permit		
57	DTREV	Draft reviewed		
58	DTDDP	Draft permit developed	01/30/2014	
59	LGNRAPP	local gov't notified of receipt of app. (Iss/Mod)		
60	DTOWN4	FS/SOB draft permit sent to owner 4th time		